

Geographical Distribution of the Space-Weaving Spider, *Chibchea salta*, from Northwestern Argentina: New Records and Bioclimatic Modeling

Authors: Rubio, Gonzalo D., and Acosta, Luis E.

Source: Journal of Insect Science, 11(54) : 1-14

Published By: Entomological Society of America

URL: <https://doi.org/10.1673/031.011.5401>

The BioOne Digital Library (<https://bioone.org/>) provides worldwide distribution for more than 580 journals and eBooks from BioOne's community of over 150 nonprofit societies, research institutions, and university presses in the biological, ecological, and environmental sciences. The BioOne Digital Library encompasses the flagship aggregation BioOne Complete (<https://bioone.org/subscribe>), the BioOne Complete Archive (<https://bioone.org/archive>), and the BioOne eBooks program offerings ESA eBook Collection (<https://bioone.org/esa-ebooks>) and CSIRO Publishing BioSelect Collection (<https://bioone.org/csiro-ebooks>).

Your use of this PDF, the BioOne Digital Library, and all posted and associated content indicates your acceptance of BioOne's Terms of Use, available at www.bioone.org/terms-of-use.

Usage of BioOne Digital Library content is strictly limited to personal, educational, and non-commercial use. Commercial inquiries or rights and permissions requests should be directed to the individual publisher as copyright holder.

BioOne is an innovative nonprofit that sees sustainable scholarly publishing as an inherently collaborative enterprise connecting authors, nonprofit publishers, academic institutions, research libraries, and research funders in the common goal of maximizing access to critical research.



Geographical distribution of the space-weaving spider, *Chibchea salta*, from northwestern Argentina: New records and bioclimatic modeling

Gonzalo D. Rubio^a and Luis E. Acosta^{b*}

CONICET, Cátedra de Diversidad Animal I, Facultad de Ciencias Exactas, Físicas y Naturales, Universidad Nacional de Córdoba, Av. Vélez Sarsfield 299, X5000JJC Córdoba, Argentina

Abstract

New records of the spider *Chibchea salta* Huber 2000 (Araneae, Pholcidae) from northwestern Argentina are provided, and the potential range of this species is modeled. Two presence-only methods, Maxent and Bioclim, were run using 19 bioclimatic parameters at a resolution of 30 arc seconds. The climatic profile of *C. salta* is described, and the relative importance of the bioclimatic variables is explored. Temperature variables proved to be more decisive to the final range shape. The range predicted with Maxent is slightly larger than with Bioclim, but the latter appears to be more sensitive to the record set bias. Both methods performed well, resulting in predictive ranges consistent with the yungas ecoregion. These results provide an initial insight into the bioclimatic tolerance of *C. salta*, and by identifying potential areas with no records, such as the sierras on the Salta-Jujuy border, they also help in identifying sites for future sampling efforts.

Keywords: Bioclim, bioclimatic profile, ecological niche modeling, Maxent, presence-only, Yungas Ecoregion

Abbreviations: **AUC**, area under curve; **bc**, bioclimatic variable; **GIS**, Geographical Information Systems

Correspondence: ^a grubio@conicet.gov.ar, ^{b*} lacosta@com.uncor.edu, *Corresponding author

Editor: Jay Rosenheim was editor of this paper

Received: 17 February 2010, **Accepted:** 20 May 2010

Copyright : This is an open access paper. We use the Creative Commons Attribution 3.0 license that permits unrestricted use, provided that the paper is properly attributed.

ISSN: 1536-2442 | Vol. 11, Number 54

Cite this paper as:

Rubio GD, Acosta LE. 2011. Geographical distribution of the space-weaving spider, *Chibchea salta*, from northwestern Argentina: New records and bioclimatic modeling. *Journal of Insect Science* 11:54 available online: insectscience.org/11.54

Introduction

Research on spiders in Argentina has been hitherto mainly restricted to taxonomic and systematic work on several families, together with a few papers referring to community and diversity studies (Liljesthröm et al. 2002; Beltramo et al. 2006; Avalos et al. 2007; Rubio et al. 2008), but none concerning the study of species responses to climate and its variation in space. Much work is still needed to understand the distribution patterns of the native fauna of spiders; and this would be especially meaningful in areas with an added conservation value (e.g. the yungas ecoregion), due to the biological diversity and the gradual loss of many of their habitats. At present, studies on Araneae aimed to tackle biogeographical questions are completely lacking in Argentina. Research at local and regional scales suggest, however, that spiders are well suited for biogeographic studies, since they are strongly influenced by the habitat type and other environmental parameters, so that their presence is fairly predictable (Uetz 1975; Weeks and Holtzer 2000; Pinkus-Rendón et al. 2006).

Novel methods that estimate species potential distributions by combining observed occurrences with environmental variables proved their effectiveness for application across a range of biogeographical analyses (Maes et al. 2005; Pearson et al. 2007). These kinds of analyses use the facilities provided by the Geographical Information Systems (GIS), and allows obtaining a first empiric approach to the range of ecophysiological tolerance through the evaluation of the bioclimatic profile, by identifying the environmental conditions and areas in which a given species would be able to survive (Pearson 2007). Such predictive models have been proposed as

useful tools to supplement incomplete data of distribution of species (Maddock and Du Plessis 1999; Raxworthy et al. 2003; Acosta 2008). All these methods assume that the resulting predictive distribution model is a function of the way in that species respond to the environmental variables, thus reflecting a subset of their fundamental niche (Austin 2002). Predictive distribution patterns and their inherent bioclimatic profiles provide valuable information for numerous ecological-environmental applications; for example, to detect areas where intensive sampling would be worthwhile or necessary, to define conservation priorities, or to predict potential biological invasions (Guisan and Zimmermann 2000; Raxworthy et al. 2003; Graham and Hijmans 2006; Ward 2007; Acosta 2008; Giovanelli et al. 2008). An extensive array of modeling algorithms is available to investigate relationships between predictor variables and species presence-only datasets (Guisan and Zimmermann 2000; Guisan and Thuiller 2005). Two of these methods, Bioclim (Fischer et al. 2001; Walther et al. 2004), and Maxent (Phillips et al. 2006) are among the most popular algorithms in the literature and have proven good performance and accuracy for these kinds of studies (Elith et al. 2006; Hijmans and Graham 2006; Ward 2007; Echarri et al. 2009; Rubio et al. 2010); both are well suited to the aims of this study.

The purpose of this paper is to provide new records and to model the potential distribution of the spider, *Chibchea salta* Huber 2000 (Pholcidae), that is characteristic of a high diversity area in northwestern Argentina, the “yungas” ecoregion. It is also aimed to visually compare the resulting prediction maps obtained with the two above-mentioned modeling methods. One major objective of

this study was to explore the climatic profile underpinning the species distribution, in order to start gathering preliminary knowledge on its niche requirements – a fact almost completely ignored for the vast majority of Neotropical spiders. *Chibchea* is a relatively small pholcid genus, currently comprised of 16 nominal species (Platnick 2009). This genus spreads over a wide range on the west of South America, from Colombia and Venezuela up to northern Argentina and Chile. It is apparently restricted to the Andean corridor, where it can inhabit over 3500 masl (e.g. *C. abiseo* from Perú) (Huber 2000). All species of *Chibchea* are small to medium-sized spiders, generally with dark colors and globose to oval, higher-than-long opisthosoma. This is the only *Chibchea* species known in Argentina, and has been recorded in just two localities within the humid subtropical yungas forests in Salta Province. It belongs to a clade that represents the southernmost distribution of the whole genus, also containing species from Peru and Bolivia: *C. aberrans*, *C. araona*, *C. uru*, *C. silvae* and *C. malkini* (Huber 2000).

Modeling the distribution of a yungas spider has an additional importance. The referred ecoregion has long been recognized to have high endemism and biodiversity rates, in Argentina only matching the Paranaense forests in Misiones Province (Brown et al. 2002). Elevation determines three definite vegetation belts in the yungas, well defined by the plant species composition and physiognomy: (1) pedemontane rainforests, (2) montane rainforests and (3) montane forests (Brown et al. 2002, 2006). The yungas ecoregion extends as a narrow strip for more than 4000 km on the eastern slopes of Andean and sub-Andean mountains (Cabrera and Willink 1973). The Argentinean portion represents the southernmost end. In this country this ecoregion is discontinuous and split into patches (Acosta 2002; Brown et al. 2006). In the Salta Province, at approximately 25° 10' S, the Chaco ecoregion (a xeric thorn-forest) ingresses into the Valle de Lerma, causing the main disruption of the yungas and its fragmentation into patches (Figure 1), thus creating a complex interface with marked

Table 1. New records of *Chibchea salta*, with geographical coordinates and sampling details

Ref.	Province	Locality	Latitude (S)	Longitude (W)	Date	Collector	Number of specimens	Sampling method	Repositories
A*	Jujuy	Calilegua National Park	-23.6678	-64.8675	06-11 Dec 2008	GR et al. 1	21	hc	MACN-Ar
					29 Nov 2008	GR & MG	1	hc	CDA 000.820
B*	Jujuy	Potrero de Yala	-24.119	-65.4561	29 Nov 2008	GR & MG	6	hc	CDA 000.821
C-D	Salta	Records by Huber (2000)							
E*	Salta	Road to El Carmen (site 1)	-24.5019	-65.3228	26-28 Apr 2006	GR et al. 2	46	G-V	IEBI, CDA 000.822
F*	Salta	Road to El Carmen (site 2)	-24.5021	-65.3265	26-28 Apr 2006	GR et al. 2	12	G-V	IEBI, CDA 000.823
G*	Salta	Road to El Carmen (site 3)	-24.5027	-65.3348	26-28 Apr 2006	GR et al. 2	15	G-V	IEBI, CDA 000.824
H	Salta	Road to El Carmen (site 4)	-24.5056	-65.3378	26-28 Apr 2006	GR et al. 2	39	G-V	IEBI, CDA 000.825
I	Salta	Road to El Carmen (site 5)	-24.5066	-65.3396	26-28 Apr 2006	GR et al. 2	9	G-V	IEBI, CDA 000.826
J*	Salta	Road to El Carmen (site 6)	-24.5228	-65.3506	26-28 Apr 2006	GR et al. 2	15	G-V	IEBI, CDA 000.827
K*	Salta	Quebrada San Lorenzo (site 1)	-24.7099	-65.5172	26-28 Apr 2006	GR et al. 2	10	G-V	IEBI, CDA 000.828
L*	Salta	Quebrada San Lorenzo (site 2)	-24.7173	-65.5171	26-28 Apr 2006	GR et al. 2	32	G-V	IEBI, CDA 000.829
M*	Salta	Quebrada San Lorenzo (site 3)	-24.7183	-65.5094	26-28 Apr 2006	GR et al. 2	24	G-V	IEBI, CDA 000.830
N*	Salta	Quebrada San Lorenzo (site 4)	-24.7195	-65.5065	26-28 Apr 2006	GR et al. 2	53	G-V	IEBI, CDA 000.831
O	Salta	Quebrada San Lorenzo (site 5)	-24.7195	-65.5043	26-28 Apr 2006	GR et al. 2	46	G-V	IEBI, CDA 000.832
P*	Salta	Quebrada San Lorenzo (site 6)	-24.7259	-65.5027	26-28 Apr 2006	GR et al. 2	22	G-V	IEBI, CDA 000.833
Q*	Salta	Cerro de la Virgen	-24.7675	-65.384	30 Nov 2008	R-L-D	3	hc	CDA 000.834
R*	Salta	Cabra Corral (site 1)	-25.2852	-65.423	26-28 Apr 2006	GR et al. 2	1	G-V	CDA 000.835
S	Salta	Cabra Corral (site 2)	-25.2861	-65.4189	26-28 Apr 2006	GR et al. 2	1	G-V	IEBI
T*	Salta	Road to Cabra Corral	-25.285	-65.2514	26-28 Apr 2006	GR et al. 2	1	G-V	IEBI
U*	Tucumán	Sierra de San Javier	-26.793	-65.3511	24 Nov 2008	GR	1	hc	CDA 000.836

References for each locality are employed in figures 1 and 2. Only asterisked localities were computed by the software as single point records, the rest being grouped as indicated by grey squares.

Latitude and longitude are given in degrees.

Collector references: GR = G. Rubio; GR & MG = G. Rubio & M. Guerra; GR et al 1 = G. Rubio, C. Grismado, M. Izquierdo, M. Burger, P. Michalik, F. Labarque, C. Mattoni, A. Ojanguren & P. Carrera; GR et al. 2 = G. Rubio, J. Corronca, B. Cava, V. Olivo & A. González-Reyes; R-L-D = G. Rubio, F. López & P. Dávalos. Sampling methods: hand collecting (hc), Garden-Vacuum (G-V).

contrasts in short distances. According to Brown et al. (2006) this central sector is an important connectivity area with high-priority for conservation. *Chibchea salta* inhabits this central sector in Salta, hence the importance of this study that utilizes a novel approach for Argentinean spiders.

Methods

Species occurrence records

All available records of *C. salta* were used, including the few references in the literature (just two records from Salta Province: 17 km N of La Caldera, -24.5030 S -65.3351 W, and 22 km N of La Caldera, -24.5011 S -65.3180 W: Huber 2000) together with our own records (Table 1). Most of the latter were obtained in an ongoing ecological study in different sites in the central portion of Salta Province using the Garden-Vacuum method (Bolger et al. 2000; Bell et al. 2002) to collect spiders on vegetation. Additional samples were obtained from other yungas sectors: Jujuy and Salta Provinces for the northern yungas, and Tucumán representing the southern part. Records were georeferenced either *in situ*, using a Map-60 Garmin-GPS, or with the use of different digital gazetteers available in the Internet (mainly Google Earth ©). This dataset was arranged to be used within a geographic information system (DIVA-GIS 5.4, Hijmans et al. 2005a). The complete dataset consisted of 21 point records (Table 1), but due to duplicate records from the same gridcell being removed by the software during the analysis, valid effective records were restricted to 15 points. The specimens examined were deposited in the following Argentinean institutions (abbreviations and curators in parentheses): Instituto para el Estudio de la Biodiversidad de Invertebrados, Universidad Nacional de Salta (IEBI, J.A. Corronca); Colección

Table 2. Summary of the bioclimatic profile of *Chibchea salta*:

Bioclimatic variables	Median	min-max	Localities with min-max
[bc1] Annual mean temperature	16.1	14.6 - 18.6	K - T
[bc2] Mean monthly T° range	14.4	10.2 - 15.4	U - RS
[bc3] Isothermality (2/7 x 100)	56.4	46.5 - 57.8	U - K
[bc4] T° seasonality (STD x 100)	390.5	382 - 433	B - T
[bc5] Max T° of warmest month	27.1	25.9 - 30.2	K - T
[bc6] Min T° of coldest month	1.7	0.0 - 5.8	K - U
[bc7] T° annual range (5-6)	25.4	21.9 - 28	U - RS
[bc8] Mean T° of wettest quarter	20.3	18.8 - 23.3	K - T
[bc9] Mean T° of driest quarter	10.9	9.5 - 13.5	K - U
[bc10] Mean T° of warmest quarter	20.3	18.8 - 23.3	K - T
[bc11] Mean T° of coldest quarter	10.9	9.5 - 12.8	K - T
[bc12] Annual precipitation	695	477 - 1060	K - U
[bc13] Precipitation of wettest month	163	123 - 220	K - U
[bc14] Precipitation of driest month	4	2 - 13	KLMRST - U
[bc15] Precipitation seasonality (CV)	107	84.5 - 114	U - K
[bc16] Precipitation of wettest quarter	430	321 - 563	K - U
[bc17] Precipitation of driest quarter	16	7 - 41	RS - U
[bc18] Precipitation of warmest quarter	422	321 - 563	K - U
[bc19] Precipitation of coldest quarter	16	7 - 46	RS - U
Altitude (m.a.s.l)	1508	941 - 1905	T - K

Median and minimum/maximum values for all 19 bioclimatic [bc] variables in the envelope.

Absolute temperature values are in degrees Celsius (°C), precipitation in mm.

Localities bearing lowest and highest bioclimatic values are referenced as in Table 1.

Nacional Aracnológica, Museo Argentino de Ciencias Naturales “Bernardino Rivadavia” (C. Scioscia and M. Ramírez); and Colección Aracnológica de la Cátedra de Diversidad Animal I, Facultad de Ciencias Exactas, Físicas y Naturales, Universidad Nacional de Córdoba (L.E. Acosta).

Environmental data

Values of 19 bioclimatic parameters were extracted from the WorldClim database (Hijmans et al. 2005b) at a resolution of 30 arc-seconds (~1 km²). These parameters (bioclimatic variables) fall into two broad categories – temperature or precipitation variables – and are listed in Table 2. Elevation data were available for reference purposes, but not used as a predictor by themselves.

Modeling methods

The geographical range of *C. salta* was modeled with two widely used, presence-only methods, Maxent and Bioclim. The Maxent algorithm (described in detail by Phillips et al. 2006) yields results ranging from 0 to 1, indicating relative suitability of a given grid

cell (high values indicate a higher presence probability) (Graham and Hijmans 2006; Phillips et al. 2006). Since probability is continuous, a threshold needs to be set to separate suitable from not suitable gridcells; in this study, the “maximum training sensitivity plus specificity” threshold rule was applied (Liu et al. 2005). Other relevant settings of the software were used in their default values, including the convergence threshold (10^{-5}); maximum background points (10,000); maximum iterations (1,500); replicated run type (subsample), output format (logistic), and “auto features” activated. Resulting predictions were visualized and mapped by importing the ASCII files into DIVA-GIS 5.4 grid format (Hijmans et al. 2005a). Version 3.3.0 of the Maxent software was employed (Phillips et al. 2009). To estimate the relative contribution of each variable in the final model a jackknife analysis was applied as a built-in functionality of Maxent (Phillips et al. 2006). The Bioclim model was built using its implementation in DIVA-GIS 5.4 (Hijmans and Graham 2006; Ward 2007; Acosta 2008; Echarri et al. 2009). Bioclim is a frequency distribution based algorithm, which extracts values of each bioclimatic variable from all localities and arranges them in a cumulative frequency distribution. The set of values of all variables defines the bioclimatic profile of the species, delimiting the so called “envelope”, i.e. the climatic conditions that bound all occurrence localities (Guisan and Zimmermann 2000; Fischer et al. 2001; Walther et al. 2004; Ward 2007). In the potential distribution maps, gridcells are scored as suitable (if within the envelope; i.e. the presence of the species can be expected) or unsuitable (if outside the envelope) (Acosta 2008). The “most limiting factor” analysis, available in Bioclim, was applied to detect, for a given gridcell, which

variable is most critical to the inclusion of that gridcell within the resulting envelope.

Model evaluation

For Bioclim, the original data set was split and a subset of 30% presence points was set apart as a test sample. Pseudo-absence points were generated from the background using DIVA-GIS. The model was then run using the remaining 70% of the original presence data (training sample), randomly resampled in 20 repetitions (Maes et al. 2005; Pearson 2007; Acosta 2008; Echarri et al. 2009). Models obtained in these repetitions were overlaid to get a first visual evaluation of their mutual consistence and with the model built using the full dataset. Subsequently, the accuracy of the model was evaluated by calculating the AUC (area under curve) in a receiver operating characteristic plot, and the maximum Kappa (max- k). AUC values vary from 0.5 (model not better than random) to 1.0 (perfect accuracy as indicative that the model can discriminate perfectly between presences and absences of records); the max- k values over 0.75 are deemed to be excellent (Louto et al. 2005; Graham and Hijmans 2006; Randin et al. 2006). In the case of Maxent models, the program routinely calculates the AUC for each run.

Additional localities sampled

To empirically test whether localities in which the species was proven to be absent are correctly classed by the models as unsuitable, additional samplings were carried out in sites that are close to the record localities but correspond to a different ecoregion, the Chaco thorn-forest. These extra samples were obtained in central Salta using the above mentioned Garden-Vacuum method (i.e. with identical sampling effort). They consisted of 11 sites (Figures 9–10): General Güemes (three sampling sites at -24.6562 S -65.0035

W; -24.654 S -64.9917 W; -24.653 S -64.9892 W), along Juramento River (three sites: -25.0894 S -65.0025 W; -25.1345 S -65.0093 W; -25.1676 S -64.9861 W), near Cabra Corral dam (three sites: -25.1219 S -65.0361 W; -25.1205 S -65.0574 W; -25.1209 S -65.0921 W), south of La Merced (-25.0501 S -65.4962 W), and Castellanos (-24.7194 S -65.4367 W). The Chaco ecoregion is characterized by xeric and semi-deciduous forests, with shrub and herbaceous strata as well; all localities except one (General Güemes) belong to the “Sierra chaco” sub-ecoregion, extended on the basal slopes of the mountains. Sierra chaco interdigitates among yungas patches, having thus an important role in the connectivity of the northern and southern yungas sectors (Brown et al. 2006). As stated, in all 11 Chaco localities *C. salta* was not recorded (Figures 9–10).

Results

New records of *Chibchea salta*

Nineteen new localities for this species, along with collection information and geographical coordinates are listed in Table 1.

Bioclimatic profile

The envelope of *C. salta*, as obtained with Bioclim, contains (with the default percentile threshold of 0.025) 66.7% of the presence records (i.e. 10 of 15 points fall within all possible bidimensional variable combinations). Table 2 summarizes the bioclimatic profile of this species by indicating minimum, maximum, and medians for all 19 bioclimatic variables. Quebrada de San Lorenzo, site 1 (K in Table 1 and Figure 1) has the highest score of extreme bioclimatic values of the envelope (n = 14). Many of these extreme values indicate this locality as the coldest and driest site (bc1, 5–6, 8–14, 16, 18), as well as with highest isothermality and

precipitation seasonality (bc3, 15); all these features were consistent with the elevation of the locality, the highest in the whole dataset (1905 m). Another locality with many extreme bioclimatic values (13 variables) is site U (San Javier, Tucumán), in this case showing the highest precipitation (bc12–14, 16–19), and lowest values of isothermality and temperature range (bc2–3, 7; see also Figure 2). Site T (road to Cabra Corral, in Salta Province), representing the record with lowest elevation and closest to the Chaco plains east of the mountains, is the warmest place (bc1, 5, 8, 10–11) and has highest temperature seasonality (bc4; Figure 2), principally due to the high values in December and January.

Potential range

Models obtained with Maxent and Bioclim overall share a similar pattern (Figures 3–4), and both, in turn, match fairly well the yungas ecoregion (Figure 1). The highest probability (Maxent) or suitability (Bioclim) is consistently situated around the central area of Salta, i.e. where most records originate (Figure 1). The area with highest climatic suitability (0.80–1) recognized by Maxent is larger, extending from central Salta (Lerma Valley, San Lorenzo) to mid-southern Jujuy (Figure 3). In contrast, the highest suitability in the Bioclim model is much more concentrated in the Lerma Valley up to San Lorenzo, but reaches southern Jujuy only weakly (Figure 4). In both models the predicted range extends southwards, bordering northern and eastern slopes near Metán sierras. Bioclim and Maxent also agree in detecting one relevant potential area on the East, with no records of the species yet, close to the El Rey National Park and along the mountain group on the Jujuy-Salta border (Figures 1, 3–4). This area comprises several contiguous Sierras, interestingly bearing a large easternmost yungas isolate; it includes a

small isolated mountain as well (Sierra de la Lumbreira), also recovered in isolation in the models (Figures 1, 3-4). Although with different intensity, both models project the species range north- and southwards. The projection into northern Salta (near the Baritú National Park area) is more continuous though with low probability in Maxent (Figure 3), whereas it is just represented by scattered dots in Bioclim (Figure 4). The southwards extension into Tucumán Province is separated from the core area in both models, and predicts one larger zone on the Northeast (Sierra de Medina) and a narrow strip on east faced slopes of the Aconquija-Calchaquíes range (Figures 3-4); only the Maxent model gives high probability on the surroundings of the sole record in that province (site U, Sierra de San Javier; Figure 1), while Bioclim remarkably ranks the latter as a marginal site bearing, as stated above, many extreme values for bioclimatic variables.

Limiting factors and relative importance of variables

Separate models were built in Bioclim with either temperature (bc1-11) or precipitation variables (bc12-19), to investigate their relative contribution to the final model (Figures 5-6). Results show that precipitation variables are clearly restrictive on the West because of the decrease of rainfall (following the increase of elevation), and partly on the South – mainly in the sub-xeric Lerma Valley in Salta Province. On the contrary, these variables are remarkably permissive towards the East into the Chaco ecoregion (part of Santiago del Estero, eastern Salta, even entering the Bolivian territory: Figure 5), showing that precipitation in this area would be enough for the species. Models obtained with temperature variables alone (bc1-11) result in a much narrower area more similar to the final model, but still with a remarkable

permissiveness into xeric mountain valleys (mainly the "Valles Calchaquíes" region, between Salta and Tucumán Provinces; Figures 1, 5) where no montane forest exists. Temperature variables are critical to the species range mostly on the southeastern and northern part of the predicted range (presumably related to a latitudinal gradient), and towards the East, in this case preventing geographical expansion into the warm (though otherwise humid enough) Chaco plains (Figures 5-6). For example, bc6 (minimum temperature of the coldest month) is the most limiting factor on the margins of the San Francisco Valley with Chaco vegetation (Jujuy; Figure 1), and a small move into the valley represents an increase of $>3^{\circ}\text{C}$ for this variable which makes it to fall outside the species envelope; bc6 is also restrictive in southern Salta and northern Tucumán where the increase can be of 5°C when moving apart from the core area into the Chaco. From another viewpoint, the jackknife analysis performed in the Maxent run indicated that three variables linked to temperature (bc5: maximum T° of warmest month, bc6: minimum T° of coldest month, and bc10: mean T° of warmest quarter) and one of precipitation (bc15: precipitation seasonality) are the most relevant when the range is considered as a whole, i.e. they show the highest gain when analyzed individually; bc6 is the variable that decreases the gain the most when omitted (Figure 8). These results emphasize the major importance of temperature variables in the final models, constraining the climatic niche within a quite narrow thermic tolerance (cf. Table 2).

Model performance and comparisons

Both Maxent and Bioclim performed well and their resulting modeled ranges are consistent to each other (Figures 3-4). The range predicted with Maxent is 35% larger than with

Bioclim, showing that in the latter, suitable gridcells tend to concentrate more around record points. The overlay of the resulting maps of 20 runs in Bioclim using training data (70% of stochastic original records) are highly consistent with the predicted range using all points. Bioclim values of AUC were of high accuracy (0.80–0.97; mean = 0.93, 20 replicates using training data), while max-*k* proved excellent performance in average (0.61–0.99; mean = 0.86, same number of replicates). In Maxent, AUC values resulting from the training data were excellent (0.998–0.999; mean = 0.998, 20 repetitions). These AUC values should be taken with caution, however, since they might be over-rated due to the low number of records. Aside from the statistical meaning, the modeling proved to be in reasonable agreement with the expected range, especially considering the distribution of yungas formations and the type of environment inhabited by this species (mountain forests and rainforests, G.D.R. pers. obs.). Although this study did not focus primarily on absence data, samplings available for 11 Chaco sites yielded no specimen of *C. salta* outside the predicted range (Figures 9–10). All Chaco sites placed east of the mountains (i.e. in the Chaco plains proper; C-D on Figures 9–10) matched negative areas of the models that reflects a correct prediction in this sector. This is especially remarkable for the row of sites along Juramento River (D) that seems to follow a narrow unsuitable corridor between suitable gridcells. These observations strongly suggest the models ability to make correct predictions on negative areas. However, this ability did not stand the same for Chaco sites placed on the west, inside the Lerma Valley: with Maxent both sites (Castellanos and south of La Merced: A-B on Figure 9) fall not only within the predicted positive area, but with high probability; in the Bioclim model, the

former site was classed among presence gridcells too, though the latter (actually placed on the very limits of the suitable area) did not.

Discussion

As in other cases (Elith et al. 2006; Pearson et al. 2007; Ortiz-Martínez et al. 2008; Boubli and de Lima 2009;), the bioclimatic analysis proved to be a valuable means to get insight of the fundamental niche features of a species with still scarce records and almost no previous ecological knowledge. Both methods performed consistently well considering that a narrow-ranged yungas species – probably a true endemics species – was used. As shown elsewhere (Rubio et al. 2010), not every yungas-dwelling spider is necessarily endemic to this ecoregion, but very little is known so a general pattern cannot be drawn. It is interesting to note that, although models were built with selected climatic variables alone, the resulting prediction redraws quite well the yungas ecoregion that is defined by vegetation physiognomy and composition. Models did not explicitly include a vegetation constraint, but vegetation is generally assumed to be a critical determinant in the presence or absence of most pholcids. In that sense, the correct prediction of absence, as matched in most Chaco sites where *Chibchea salta* was “absent”, gives an additional support of the soundness of the models. This predictive value is in general appreciated as a remarkable strength of ecological niche modeling (Muñoz et al. 2009).

In accordance with results obtained for a harvestman species (Acosta 2008), temperature has proven to be more determinant to the final range shape—of *Chibchea salta*, assuming sufficient humidity. In this case, the modeled area has meaningful altitudinal differences in short distances, so

that both temperature and precipitation gradients consist of step changes that limit distribution on east and west sides. This close relationship of the range of *C. salta* and elevation (actually by means of the climatic gradient determined thereby) is common to other yungas taxa as well, as evidenced by the already mentioned altitudinal belts of this ecoregion (Brown et al. 2006). These features are no doubt well depicted in the models due to the fine grain resolution used (Acosta 2008).

Potential distributions yielded by two quite different methods, Bioclim and Maxent, are fairly consistent. As commonly suggested, no single modeling method is thought to have the complete truth (Elith et al. 2006; Stockman et al. 2006; Ward 2007), so that comparative analyses like this may help to gain a better understanding. Ranges obtained with Bioclim, despite its lower computational performances, probably look biogeographically more realistic for a species that has been observed to be closely dependent on humid forests. This is best exemplified in the Lerma Valley in Salta Province, where Maxent gives high probability to some areas known to be covered by Chaco vegetation; this portion, in contrast, was only weakly predicted in Bioclim, in better accordance to known biological facts. In turn, all Chaco localities east of the sierras (General Güemes, Juramento River) were correctly assigned as negative in both models. The correct assignment of unsuitability along the Juramento corridor is remarkable, since these Chaco sites are placed in a geographically intricate region where striking contrasts can be observed over very small distances (there are several sectors where opposite slopes at a single point may differ sharply, bearing yungas vegetation on one side and Chaco on the other). It seems clear that the climatic conditions in the Lerma

Valley – surrounded by mountains instead of being freely exposed to eastern air masses and humidity – are peculiar, and might eventually compromise the accuracy of the climatic layers (generated by extrapolation; Hijmans et al. 2005b), leading the models to wrong predictions in that area.

In any case, Bioclim appears to be more sensitive to the record set bias and to concentrate more in areas where point density is higher. It proved to be especially sensitive to outliers, as shown in the northern and southern portions of the potential range, hardly recovered by this method despite the fact that actual records are available (see Acosta 2008 for similar results). Both Bioclim and Maxent agree in detecting a presumable high suitability area, where the species has not been recorded yet: the isolated sierras group on the East, near the El Rey National Park. This is an extensive though still little surveyed yungas sector, and our results clearly point to it as a priority area to be targeted in future sampling efforts. These results are thus not deemed to be a complete picture of the range and the climatic niche of this spider, but rather provide a starting point for further research.

Acknowledgements

This contribution is a part of the Ph.D. thesis of G.D.R. (Universidad Nacional de Córdoba under advice of L.E.A.). G.D.R. was supported by a research scholarship given by the Argentinean Consejo Nacional de Investigaciones Científicas y Técnicas - CONICET. Additional funding was given to L.E.A. by CONICET (P.I.P. 2010-2012) and SECyT (Secretaría de Ciencia y Técnica, Universidad Nacional de Córdoba). L.E.A. is a researcher of CONICET. We thank José A. Corronca (IEBI-Universidad Nacional de Salta, Argentina) for enabling us to study

samples of *C. salta* obtained during the project directed by M. C. Coscarón (P.I.P. N° 5261, CONICET).

References

- Acosta LE. 2002. Patrones zoogeográficos de los Opiliones argentinos (Arachnida: Opiliones). *Revista Ibérica de Aracnología* 6: 69-84.
- Acosta LE. 2008. Distribution of *Geraecormobius sylvarum* (Opiliones, Gonyleptidae): Range modeling based on bioclimatic variables. *The Journal of Arachnology* 36: 574-582.
- Austin MP. 2002. Spatial prediction of species distribution: an interface between ecological theory and statistical modelling. *Ecological Modelling* 157: 101-118.
- Avalos G, Rubio GD, Bar ME, González A. 2007. Arañas (Arachnida: Araneae) asociadas a dos bosques degradados del Chaco húmedo en Corrientes, Argentina. *International Journal of Tropical Biology* 55(3-4): 899-909.
- Bell JR, Haughton AJ, Boatman ND, Wilcox A. 2002. Do incremental increases of the herbicide glyphosate have indirect consequences for spider communities? *Journal of Arachnology* 30: 288-297.
- Beltramo J, Bertolaccini I, González A. 2006. Spiders of soybean crops in Santa Fe province, Argentina: influence of surrounding spontaneous vegetation on lot colonization. *Brazilian Journal of Biology* 66(3): 891-898.
- Bolger DT, Suarez AV, Crooks KR, Morrison SA, Case TJ. 2000. Arthropods in urban habitat fragments in Southern California: area, age, and edge effects. *Ecological Applications* 10(4): 1230-1248.
- Boubli JP, de Lima MG. 2009. Modeling the geographical distribution and fundamental niches of *Cacajao* spp. and *Chiropotes israelita* in Northwestern Amazonia via a maximum entropy algorithm. *International Journal of Primatology* 30: 217-228.
- Brown AD, Grau A, Lomascolo T, Gasparri N. 2002. Estrategia de conservación para las selvas subtropicales de montaña (yungas) de argentina. *Ecotrópicos* 15(2): 147-159.
- Brown AD, Martínez-Ortíz U, Acerbi M, Corcuera J. 2006. *La situación ambiental argentina 2005*. Fundación Vida Silvestre Argentina.
- Cabrera AL, Willink A. 1973. *Biogeografía de América Latina*. Monografía 13, Serie de Biología, Washington, Columbia, USA, Organización de Estados Americanos.
- Echarri F, Tambussi C, Acosta-Hospitaleche C. 2009. Predicting the distribution of the crested tinamous, *Eudromia* spp. (Aves, Tinamiformes). *Journal of Ornithology* 150: 75-84.
- Elith J, Graham CH, Anderson RP, Dudík M, Ferrier S, Guisan A, Hijmans RJ, Huettman F, Leathwick JR, Lehmann A, Li J, Lohmann LG, Loiselle BA, Manion G, Moritz C, Nakamura M, Nakazawa Y, Overton JM, Peterson AT, Phillips SJ, Richardson KS, Scachetti-Pereira R, Schapire RE, Soberón J, Williams S, Wisz MS, Zimmermann NE. 2006. Novel methods improve prediction of species' distributions from occurrence data. *Ecography* 29: 129-151.

- Fisher J, Lindenmayer DB, Nix HA, Stein JL, Stein JA. 2001. Climate and animal distribution: a climatic analysis of the Australian marsupial *Trichosurus caninus*. *Journal of Biogeography* 28: 293-304.
- Giovanelli JGR, Haddad CFD, Alexandrino J. 2008. Predicting the potential distribution of the alien invasive American bullfrog (*Lithobates catesbeianus*) in Brazil. *Biological Invasions* 10: 585-590.
- Graham CH, Hijmans RJ. 2006. A comparison of methods for mapping species ranges and species richness. *Global Ecology and Biogeography* 15: 578-587.
- Guisan A, Thiller W. 2005. Predicting species distribution: offering more than simple habitat models. *Ecology Letters* 8: 993-1009.
- Guisan A, Zimmermann NE. 2000. Predictive habitat distribution model in ecology. *Ecological Modelling* 135: 147-186.
- Hijmans RJ, Graham CH. 2006. The ability of climate envelope models to predict the effect of climate change on species distributions. *Global Change Biology* 12: 1-10.
- Hijmans RJ, Guarino L, Jarvis A, O'Brien R, Mathur P, Bussink C, Cruz M, Barrantes I, Rojas E. 2005a. *DIVA-GIS, version 5.2*. Available online, <http://www.diva-gis.org/>
- Hijmans RJ, Cameron SE, Parra JL, Jones PG, Jarvis A. 2005b. Very high resolution interpolated climate surfaces for global land areas. *International Journal of Climatology* 25: 1965-1978. Available online, <http://www.worldclim.org/>
- Huber BA. 2000. New world pholcid spiders (Araneae: Pholcidae): a revision at generic level. *Bulletin of the American Museum of Natural History* 254: 1-348.
- Liljeström G, Minervino E, Castro D, Gonzalez A. 2002. La comunidad de arañas del cultivo de soja en la provincia de Buenos Aires, Argentina. *Neotropical Entomology* 31(2): 197-210.
- Liu C, Berry PM, Dawson TP, Pearson RG. 2005. Selecting thresholds of occurrence in the prediction of species distributions. *Ecography* 28: 385-393.
- Louto M, Pöyry J, Heikkinen RK, Saarinen K. 2005. Uncertainty of bioclimate envelope models based on the geographical distribution of species. *Global Ecology and Biogeography* 14: 575-584.
- Maddock A, Du Plessis MA. 1999. Can species data only be appropriately used to conserve biodiversity? *Biodiversity and Conservation* 8: 603-615.
- Maes D, Bauwens D, De Bruyn L, Anselin A, Vermeersch G, Van Landuyt W, De Knijf G, Gilbert M. 2005. Species richness coincidence: conservation strategies based on predictive modelling. *Biodiversity and Conservation* 14: 1345-1364.
- Muñoz, MES, De Giovanni R, Siqueira, MF, Sutton T, Brewer P, Pereira RS, Canhos DAL, Canhos, VP. 2009. openModeller: a generic approach to species' potential distribution modelling. *Geoinformatica* (DOI 10.1007/s10707-009-0090-7).
- Olson DM, Dinerstein E, Wikramanayake ED, Burgess ND, Powell GVN, Underwood EC, D'Amico JA, Strand HE, Morrison JC, Loucks CJ, Allnutt TF, Lamoreux JF, Ricketts TH, Itoua I, Wettengel WW, Kura Y, Hedao

P, Kassem K. 2001. Terrestrial ecoregions of the world: a new map of life on Earth. *BioScience* 51: 933-938.

Ortiz-Martínez T, Rico-Gray V, Martínez-Meyer E. 2008. Predicted and verified distributions of *Ateles geoffroyi* and *Alouatta palliata* in Oaxaca, Mexico. *Primates* 49: 186-194.

Pearson RG. 2007. *Species' distribution modeling for conservation educators and practitioners. Synthesis*. American Museum of Natural History. Available online, <http://ncep.amnh.org> and http://biodiversityinformatics.amnh.org/files/SpeciesDistModelingSYN_1-16-08.pdf

Pearson RG, Raxworthy CJ, Nakamura M, Peterson AT. 2007. Predicting species distributions from small numbers of occurrence records: a test case using cryptic geckos in Madagascar. *Journal of Biogeography* 34: 102-117.

Phillips SJ, Anderson RP, Schapire RE. 2006. Maximum entropy modeling of species geographic distributions. *Ecological Modeling* 190: 231-259.

Phillips SJ, Dudik M, Schapire RE. 2009. Maxent (Maximum Entropy Modeling of Species Geographic Distributions). Version 3.3.0-beta, April 2009. Available at <http://www.cs.princeton.edu/~schapire/Maxent/>.

Pinkus-Rendón MA, León-Cortés JL, Ibarra-Núñez G. 2006. Spiders diversity in a tropical habitat gradient in Chiapas, Mexico. *Diversity and Distributions* 12: 61-69.

Platnick N. 2009. *The World Spider Catalog, version 10.0*. American Museum of Natural

History, New York. Available online, <http://research.amnh.org/entomology/spiders/catalog/index.html>

Randin CF, Dirnböck T, Dullinger S, Zimmermann NE, Zappa M, Guisan A. 2006. Are niche-based species distribution models transferable in space? *Journal of Biogeography* 33: 1689-1703.

Raxworthy CJ, Martínez-Meyer E, Horning N, Nussbaum RA, Schneider GE, Ortega-Huerta MA, Peterson AT. 2003. Predicting distributions of known and unknown reptile species in Madagascar. *Nature* 426: 837-841.

Rubio GD, Corronca JA, Damborsky MP. 2008. Do spider diversity and assemblages change in different contiguous habitats? A case study in the protected habitats of the Humid Chaco ecoregion, northeast Argentina. *Environmental Entomology* 37: 419-430.

Rubio GD, Rodrigues ENL, Acosta LE. 2010. Description of the male of *Dubiaranea difficilis* (Araneae: Linyphiidae), with new records and modeling of its potential geographic distribution. *Zootaxa* 2405: 55-62.

Stockman AK, Beamer DA, Bond JE. 2006. An evaluation of a GARP model as an approach to predicting the spatial distribution of non-vagile invertebrate species. *Diversity and Distributions* 12: 81-89.

Uetz GW. 1975. Temporal and spatial variation in species diversity of wandering spiders (Araneae) in deciduous forest litter. *Environmental Entomology* 4: 719-724.

Walther BA, Wisz MS, Rahbek C. 2004. Known and predicted African winter distributions and habitat use of the endangered Basra reed warbler (*Acrocephalus griseldis*)

and the near-threatened cinereous bunting (*Emberiza cineracea*). *Journal of Ornithology* 145: 287-299.

Ward DF. 2007. Modeling the potential geographic distribution of invasive ant species in New Zealand. *Biological Invasions* 9: 723-735.

Weeks RD Jr, Holtzer TO. 2000. Habitat and season in structuring ground-dwelling spider (Araneae) communities in a shortgrass steppe ecosystem. *Environmental Entomology* 29(6): 1164-1172.




Figure 1. Locality records of *Chibchea salta* Huber 2000 (blue triangles), and extent of the yungas montane forest ecoregion (green area) in northwestern Argentina (from Olson et al. 2001). References: 1: Baritú National Park; 2: San Francisco Valley; 3: El Rey National Park; 4: Lerma Valley in Central Salta; 5: Sierra de la Lumbreira; 6: Sierras de Metán; 7: Valles Calchaquies; 8: Sierra de Medina; 9: Sierra del Aconquija/Cumbres Calchaquies. Localities (letters) are as listed in Table I. Inset: location of the map area in South America. High quality figures are available online.




Figure 2. Bioclimatic profile of *Chibchea salta*: for each bioclimatic variable, cumulative relative frequencies (0–100) are displayed for the full data set. Blue dots indicate outlier localities, their references are the same as listed in Table I. High quality figures are available online.




Figure 3-4. Predicted range of *Chibchea salta*, as resulted in the Maxent (Figure 3) and Bioclim (Figure 4) analyses using all 19 bioclimatic variables and the full dataset. Code colors indicate either climatic or habitat suitability: Maxent (Figure 3, shown as probability): red (0.90–1), orange (0.80–0.90), green (0.65–0.80), light blue (0.50–0.65); Bioclim (Figure 4, as cumulative distribution percentile): red (20–34), orange (10–20), green (5–10), light blue (2.5–5). High quality figures are available online.




Figure 5-6. Potential distribution of *Chibchea salta* modeled with Bioclim, only with temperature variables (bc1–bc11; Figure 5) or precipitation variables (bc12–bc19; Figure 6), using the full dataset. Color codes are the same as those listed in Figures 3 and 4. High quality figures are available online.




Figure 7-8. Contribution of bioclimatic variables to the final model. Figure 7: Most limiting factors analysis of *Chibchea salta* using Bioclim; gridcells where temperature variables are limiting are colored in orange, those limited by precipitation variables are in blue. Figure 8: Jackknife of the regularized training gain (Maxent model): without variable (light blue), with only variable (blue), with all variables (red). High quality figures are available online.




Figure 9-10. Close-up of the central portion of the predicted range of *C. salta* (between parallels -24.51° and -25.28° S) showing the position of all 11 Chaco sites (black triangles) available for assessment of the negative predictions. They are contrasted with the areas predicted by Maxent (Figure 9) and Bioclim (Figure 10). References: A = Castellanos, B = near La Merced (A and B placed in the Lerma Valley), C = General Güemes, D = Juramento River and road to Cabra Corral Dam. Remark: in Figure 10, point B actually falls inside a negative gridcell, though the scale used does not allow this fact to be easily seen. High quality figures are available